



Ogle County Highway Department

Jeremy A. Ciesiel, P.E., County Engineer
1989 South IL Route 2
Oregon, IL 61061

March 28, 2019

**Project: Ogle County
Daysville Road
Section 19-XX000-XX-GM**

NOTICE TO PROSPECTIVE BIDDERS – ADDENDUM #1

The following serves as an addendum notice for the project. This information supersedes all conflicting information contained within the contract proposal and specifications. All Contractors must use the information and corrected pages in completing their bids.

Item 1:

Please refer to BLR 12200a – Schedule of Prices provided in the Local Public Agency Formal Contract Proposal. Please revise to include item 10 – **WV Adjust - 2 Each**.

The revised BLR 12200a form is attached and shall be used for all bid submittals. A revised Summary of Quantities page is also included.

The following Special Provision shall be used for this pay item:

WATER VALVES TO BE ADJUSTED

This work shall be performed in accordance with Section 602 of the Standard Specifications for Road and Bridge Construction. The Contractor shall verify that all valves castings are within the proposed cross-slope prior to surface paving. The Contractor shall notify the City of Oregon if any broken castings are found during adjustment operations.

This work shall be paid for at the contract unit price per EACH for WATER VALVES TO BE ADJUSTED.

Item 2:

Paving Clarification - The existing cross-slope of Daysville Road, from Mix Lane to 650' south of Mix Lane, is flat or has backfall towards the centerline in the northbound lane. The Contractor is advised that the crown of the roadway shall be adjusted in this section to maintain a 2% minimum cross-slope from the centerline to the edge of pavement during paving operations. The Contractor shall also note that edge milling shall be required along the existing v-gutters south of Mix Road, as shown in the contract details.

Please include this addendum notice with your bid submission as acknowledgement of receipt of Addendum #1.

Respectfully submitted,

A handwritten signature in black ink, appearing to read "Shaun M. Gallagher". The signature is fluid and cursive, with a long horizontal stroke at the end.

Shaun M. Gallagher, P.E.
Asst. County Engineer

END OF ADDENDUM #1



SCHEDULE OF PRICES

County Ogle
 Local Public Agency Various
 Section 19-XX000-00-GM
 Route Daysville Road

Schedule for Multiple Bids

Combination Letter	Sections Included in Combinations	Total

Schedule for Single Bid

(For complete information covering these items, see plans and specifications)

Bidder's Proposal for making Entire Improvements
--

Item No.	Items	Unit	Quantity	Unit Price	Total
1	Hot Mix Asphalt Surface Course	Ton	1802		
2	Hot Mix Asphalt Leveling Binder	Ton	965		
3	HM Asphalt Incidental Surface	Ton	124		
4	Bituminous Materials (Tack Coat)	LB	6100		
5	Aggregate Shoulders, Type B	Ton	629		
6	HM Surface Removal-Butt Jt	SY	1852		
7	Temporary Pavement Markings	Ft	978		
8	Pavement Marking Line 4"	Ft	17510		
9	Traffic Control and Protection	LS	1		
10	WV Adjust	Ea	2		

SUMMARY OF QUANTITIES
Sections 19-00000-00-GM, 19-21000-00-GM, and 19-26000-00-GM
City of Oregon, Rockvale and Oregon-Nashua Townships
Daysville Road

<u>Item</u>	<u>Unit</u>	<u>Quantity</u>
Hot-Mix Asphalt Surface Course	TON	1,802
Hot-Mix Asphalt Leveling Binder	TON	965
Hot-Mix Asphalt Incidental Surface	TON	124
Bituminous Materials, (Tack Coat)	LB	6,100
Aggregate Shoulders, Type B	TON	629
Hot Mix Surface Removal – Butt Joint	Sq. Yd.	1,852
Temporary Pavement Markings	Foot	978
Pavement Marking Line 4”	Foot	17,510
Traffic Control & Protection	LS	1
Water Valve Adjust	EA	2